

Virgo status and commissioning results

L. Di Fiore

for the Virgo Collaboration



5th LISA Symposium – 13 july 2004

VIRGO is an French-Italian collaboration for Gravitational Wave research with a 3 km long ground-based interferometer.

ITALY - INFN

- Firenze-Urbino
- Frascati
- Napoli
- Perugia
- Pisa
- Roma

FRANCE - CNRS

- ESPCI – Paris
- IPN – Lyon
- LAL – Orsay
- LAPP – Annecy
- OCA - Nice


Virgo is located in Cascina, a small town close to Pisa,
at the European Gravitational Observatory (EGO)




EGO is a Consortium settled up by the CNRS and the INFN

• Main objectives of EGO


- 1) to support the commissioning of Virgo, its operation, maintenance and upgrades**
- 2) to create and run a computing center for the analysis of data,**
- 3) to ensure the maintenance of the site and the related infrastructures**
- 4) to promote R&D useful for the detection of gravitational waves**



The Virgo Interferometer



Planned Sensitivity



Vacuum System

- Two tubes: 3 km long, 1.2 m in diameter, installed and tested, in vacuum since June 2003, 10^{-6} mbar
- All tower (6 long, 2 short) pumping systems: installed, tested and put in operation, 10^{-9} mbar




Tubes



Towers

Laser system

- 20W, Nd:YVO4 laser, two pumping diodes
- Injection locked to a 1W Nd:YAG master laser
- Required power stability: 10^{-8}
- Required frequency stability: μHz






Input Mode Cleaner

- Triangular cavity, 144 m long, Finesse=1000
- Input optics and two flat mirrors are located on a suspended optical bench
- End mirror suspended with a reference mass for actuation
- Transmission 50%




Detection System

- Suspended bench in vacuum with and the output mode cleaner (OMC)
- Detection, amplification and demodulation on external bench



Virgo Mirrors



- Material: fused silica
- Dimension: 35 cm diameter, 10 cm thick
- Mass: ~ 21 Kg
- Substrate losses: 1 ppm
- Coating losses: <5 ppm
- Surface deformation: $\lambda/100$ (rms on 150mm)



Suspension System


The **Super-attenuator** (SA) is a multi-stage seismic attenuator with an inverted pendulum as pre-isolator

Expected attenuation @10 Hz > 10^{14}




Suspension System

Pre-isolator



aluminum
 accelerometers and LVDT
 for Inertial damping
 suspension point (used for tide)




Suspension System

passive filters



after the pre isolator there are 5 passive filter supported by steel wires

Vertical isolation is provided blade-springs with magnetic anti-springs



Suspension System

Payload



13 July 2004

5th LISA Symposium - L. Di Fiore

Suspension and mirror control


A very important issue is the distribution of control forces along the attenuator chain

The error signals come from both local references (local controls) or global control (interferometer signals)

Mirror with RM coils:

- payload NM damping (optical levers with PSD)
- ITF Locking (fast)

- ITF alignment




Local Controls

sensors: CCD Camera and PSDs

The control is automatically switched from CCD to PSD according to oscillation amplitude

Control of mirror angular position
(residual motion $< 1 \mu\text{rad rms}$)

Damping of mirror longitudinal oscillations
(useful for lock acquisition)



Present status

milestones of Virgo construction

1996 - 1998 - Construction of central area

**1999 - 2002 - Construction of the arms and the terminal buildings
Installation and commissioning of the central interferometer**

2001 - 2003 - Vacuum tubes installation

2002 - 2003 - Installation of final mirrors and of terminal suspensions

June 2003 - last mirror installed

July 2003 - Virgo inauguration

2003 - Start detector commissioning




Commissioning plan overview

- Phase A: Commissioning of interferometer arms
- Phase B: Commissioning of the recombined interferometer
- Phase C: Commissioning of the recycled interferometer

Status today:

- phase B near to completion
- moving to phase C



13 July 2004

5th LISA Symposium - L. Di Fiore



Phase A: Fabry-Perot cavities

Commissioning of interferometer arms


- Test all aspects of control systems in a simple optical configuration
 - locking
 - automatic alignment
 - second stage of laser frequency stabilization
 - suspension hierarchical control
- Verify the performances of the various sub-systems:
 - injection, detection, global control, DAQ, data storage, ...
 - make the list of problems to be solved in a following phase (do not get stuck on a problem, if possible !)

Phase A1: Commissioning of north arm

- Verify functioning of NI and NE suspension controls

Phase A2: Commissioning of west arm

- Verify functioning of WI, WE and part of BS suspension controls





Phase B: Recombined Interferometer

Commissioning of interferometer in ‘recombined mode’

- Useful intermediate step towards full interferometer lock
 - Start noise investigations
- ⇒ make the list of problems to be solved in a following phase




Phase B1: Lock Michelson interferometer

- Verify functioning of BS longitudinal control



Phase B2: Operate Fabry-Perot Michelson interferometer

- Verify understanding of lock acquisition and linear alignment
- Start noise investigations (hopefully others than laser noises)



13 July 2004

5th LISA Symposium - L. Di Fiore



Phase C: Recycled Interferometer

Commissioning of Recycled Fabry-Perot interferometer

- Test full locking acquisition process
- Implement complete wave-front sensing control
- Noise hunting




Phase C1: Lock central interferometer

- First step of lock acquisition
- Verify PR mirror longitudinal control
- Check recycling gain



Phase C2: Lock & Operate full interferometer




13 July 2004

5th LISA Symposium - L. Di Fiore


North Cavity locking

Phase A: the two arm cavities are used separately, starting with the north arm; control systems are to be installed and tested.




Automatic alignment: principle

- Anderson technique:
 - Modulation frequency coincident with cavity TEM₀₁ mode
 - Two quadrants looking at the cavity transmission (at two different Guoy phases)
 - Four signals to control the 2x2 mirror angular positions (NI & NE)



Automatic alignment: results

- Automatic alignment operated on both arms
 - bandwidth $\sim 3\text{-}4$ Hz
 - control precision ~ 0.5 μrad
- It allows to:
 - switch completely OFF local controls on all four cavity mirrors
 - stabilize power stored in the cavity
 - increase locking duration




Recombined Interferometer

Phase B:




Recombined Interferometer

- B2 (P) used to control common mode ($L1+L2$)
- B2 (Q) used to control beam splitter
- B1/B1' used to control differential mode ($L1-L2$)



Tide Control

- Earth tide > Mirror actuators range ($\sim 100 \mu\text{m}$)
- Move low frequency component of the correction to the top of the inverted pendulum




13 July 2004

5th LISA Symposium - L. Di Fiore

Laser frequency stabilization

- First test with North arm cavity
 - North cavity error signal sent to the input mode-cleaner (below 200 Hz) and to the laser (above 200 Hz)
 - Reference cavity error signal used to control cavity length at DC



Commissioning Runs

Continuous data taking periods are scheduled every second month:

- **C1: 14.-17. November 2003**
 - North arm cavity longitudinally controlled
- **C2: 20.-23. February 2004**
 - North arm cavity with longitudinal and angular control
- **C3: 23.-27. April 2004**
 - **Recombined interferometer**
 - North arm with second stage of frequency stabilisation
- **C4: 24.-29. June 2004**
 - Recombined interferometer with angular control and second stage of frequency stabilisation


Phase A (single cavity): C1, C2 & C3

- Each run last 3-4 days
- Goals:
 - Verify ITF cavities performances on longer time scales
 - Provide real data to the collaboration

- C1 (14-17/11/2003)
 - North cavity and OMC locked


- C2 (20-23/02/2004)
 - C1 + Automatic alignment
 - West arm locked

- C3 (23-27/04/2004)
 - C2 + Laser frequency stabilization



Phase B (recombined ITF): C3 & C4

- Interferometer locked with B1 and B2
- Output mode-cleaner locked to the TEM00 mode
- Automatic alignment on both arms
- Tidal control on both arms
- Laser frequency stabilized to cavities common mode
- ITF common mode locked to reference cavity






C4 run

- Configuration: recombined ITF with ‘nearly’ complete control system
- Duration: 5 days, 24-29 June 2004
- Test periods at the beginning and at the end of the run
- 9 losses of lock during quiet periods (all understood, one due to an earthquake in Alaska)
- Longest locked period: ~ 28 h, relatively stable noise level


Spectrogram_spectro_Pr_B1_ACp_300_500_0_625_start=772127004 (Thu Jun 24 15:43:24 2004)



GPS T0: 24/06/04 15:43:44




C4 run: ITF sensitivity






C4 run: Noise Sources





Next steps

- **Lock recycled interferometer**



- Present status:

- State 2: locked

- State 3: locked for 10 min with WE mirror misaligned

- Potential problem due to light backscattered inside the input mode-cleaner

- Short term solution: reduce light entering the interferometer

- Mid-term solution: add optical isolation between the interferometer and the IMC

- **Force re-allocation to marionetta (for reducing DAC noise effect)**

This topic is under study and test will start in the immediate future

Conclusion

- Construction of Virgo Completed
- Commissioning started October 2003
- Commissioning of recombined interferometer almost completed
- Commissioning of recycled interferometer starting
- Some upgrade of input bench are necessary (end of 2004 ?)
- Goal: first Scientific Run during 2005